

Pump Station #3 Improvements & Transmission Main CIP # 88039-2



Last updated: June 2026

PROJECT SCHEDULE

Design Start
Summer 2020

Design Finish
Spring 2025

Construction Start
Late Fall 2025

Construction Completion
Spring 2027

PROJECT DETAILS

Design Consultant
Ardurra

Design Contract Cost
\$1,999,490.00

Contractor
DeJonge Excavating
Contractors, Inc.

Construction Contract Cost
\$16,977,807.50

COUNTY PROJECT MANAGER(S)

Design
Nancy Brooking
nbrooking@scgov.net

Construction
Kathryn Mol
kmol@scgov.net

Project Description

The installation of approximately 10,600 linear feet (LF) of 30-inch diameter potable water by open cut and horizontal directional drill methods along Ashton Road and Ruby Lane. The new pipeline will connect the existing 30-inch water transmission main along the Legacy Trail and terminate at Sarasota County's Pump Station No. 3 (PS3). The project also includes installation of approximately 10,500 LF of 3-inch fiber optic conduit, modifications to the PS3 yard piping and valves to the existing ground storage tanks. This will allow the new 30-inch potable water transmission main to fill the ground storage tanks.

Project Progress/ Status

The design of the project is complete, and the construction contract was awarded in mid-August 2025. Construction started in late Fall 2025, and submittals have begun. Pipe and material deliveries have also commenced and will continue over the next several months. Contractor will be mobilizing to the site the beginning of February. Pipe work will begin at the pump station off of Ruby Lane and near the Ashton Trail Head Park. Horizontal drilling operations near the Ashton Trailhead Park are anticipated to be complete this month which include pulling back of the HDD pipe. Residents affected by this work will be notified. There will still be an intermittent lane closure of the west bound lane of Ashton Road, west of McIntosh Road as crews finish drilling activities and testing of the HDD pipe. This month, the drilling crew will also be mobilizing the drill near County Place Blvd and Country Side Rd to start drilling operations to the east. Please be mindful of work in the area.

